

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Wasinger "A" No. 3

SEC. 21 T. 11 R. 18W
SE SE SW
330' N & 330' W S/4 Corner

Total Depth. 3594'


County. Ellis
KANSAS

Comm. 1-15-49 Comp. 2-16-49

Shot or Treated. Acid. W/1000 gals. 3590 2-14-49, W/1500 gals. 3594 2-19-49

Contractor. Lohmann-Johnson Drlg. Co.

Issued. 4-30-49



Elevation. 2050 Ind.

CASING:

8-5/8" 1290' Cem. W/600 Sx.

5-1/2" 3582' Cem. W/150 Sx.

Production. Phy. Pot. 233 oil, no
wtr., 24 hrs.

Figures Indicate Bottom of Formations.

shale & sand	1034
red bed	1073
red bed & sand	1280
anhydrite	1325
red bed	1360
shale & shells	1410
shale	1650
sand & shale	1700
lime & shale	1810
sand, shale & lime	1980
shale & sand	2005
lime & shale	2295
lime	2340
lime & shale	3200
lime	3582
3582 RTD = 3583 SLM	
lime	3594
Total Depth	

Tops, Corr.:

Lansing	3254
Conglomerate	3538
Simpson Sand	3551
Simpson Shale	3557
Arbuckle	3581
Penetration	13

Fillup:

50' oil 1-3/4 hrs. 3587'
100' oil 2-3/4 hrs.
140' oil 3-3/4 hrs.
215' oil 7-1/4 hrs. 3590'
270' oil 8-1/4 hrs.

2-14-49 Az. W/1000 gals.

Pmpd. 70 oil, 1% wtr, 12 hrs.

2-16-49 Deepened 3590-3594'

2-19-49 Az. W/1500 gals.