

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- **CITIES SERVICE OIL CO.**
 Farm- **Wasinger "A"** No. **5**

SEC. **21** T. **11** R. **18W**
 NE NW SW
 330 S & 990' E of W/4 cor.

Total Depth. **3460 SLM**
 Comm. **9-4-54** Comp. **9-18-54**
 Shot or Treatment.
 Contractor. **Lohmann-Johnson Drlg.**
 Issued. **10-23-54**

County **Ellis**

KANSAS



Elevation. 1922

Production **31 oil, 37 water**

CASING:

8 5/8" 1227 com. w/800 sx.
5 1/2" 3456 com. w/125 sx.

Figures Indicate Bottom of Formations.

shale	725
shale & sand	760
sand	910
red bed	1080
red bed & shells	1214
anhyd.	1244
shale & shells	1365
shale & red bed	1630
salt & shale	1740
shale & shells	1830
shale & lime	2425
lime & shale	3228
lime	3270
lime & shale	3303
lime	3335
lime & shale	3450
cored shale	3456
cored shale & lime	3462
lime	3465
Total Depth	3465 RTD = 3460 SLM

Tops: Corr.

Topeka	2885
Heebner	3111
Dodge	3133
Lansing	3154
Cherty Congl.	3400
Simpson shale	3422
Simpson sand	3425
Simpson dolo.	3428
Arbuckle	3455

140' fluid in 1 hr.
1129' fluid (370' oil and 759
wtr) in 14 hrs.