


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - LARIO OIL & GAS COMPANY
Farm Henderson "E" No. 6

SEC. 22 T. 11 S. 18W
NE NW NE

Total Depth. 3505 PB 3112'
Comm. 9-16-49 Comp. 10-5-49
Shot or Treated.
Contractor. Prime Drlg. Co.
Issued. 3-25-50

County. Ellis
KANSAS



Elevation. 1954 *ft*

Production. Pot 445 bbls. trace water

CASING:

8 5/8" 1240' cem w/600 sx.
5 1/2" 3501' D.F.

Figures Indicate Bottom of Formations.

surface clay, sand	100
shale	230
shale, shells	540
sand	630
iron	650 ✓
iron, shale, sand	710 ✓
shale, shells	730
sand	825
shale, shells	970
red bed, shells, shale	1237
anhyd.	1270
red bed, shale, shells	1500
shale, shells	1645
salt, shells	1825
shale, shells	1845
shale, lime	2920
lime	3430
lime, shale	3500
arbuckle	3505
Total depth PB 3112'	

Tops: D.F.	
Anhydrite	1235
Topeka	2914
Heebner	3139
Dodge	3159
Lansing	3181
Conglomerate	3429
Simpson	3455
Arbuckle	3500

Lane Wells plug at 3112'
Perf. 17/3074-78'.
500 acid.
2000 acid.
Pot/445 bbls from Topeka, trace wtr.