


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - G. W. KEYES DRILLING CO. ET AL  
Farm - Marshall No. 1

SEC. 25 T. 11 R. 18W  
NWc NW

Total Depth. 3626'  
Comm. 5-22-47 Comp. 6-14-47  
Shot or Treated.  
Contractor.  
Issued. 8-23-47

County. Ellis  
KANSAS



CASING:  
13-3/8" 137'  
5-1/2" 3622'

Elevation. 2088' *at x rh*

Production. Pot. 3458 BO

Figures Indicate Bottom of Formations.

rock & shale	70
shale	520
sand & shells	650
sand	740
shale, sand & shells	850
salt	1000
shale & shells	1050
shells	1128
shale red	1320
anhydrite	1372
shale	1565
shale & shells	1685
salt & shale	1700
salt, shale & shells	1906
shale & shells	1945
lime	2075
lime brkn	2180
shale	2200
lime brkn	2270
lime & shale	2545
lime	2594
lime brkn	2655
lime	2710
lime & shale	2769
lime brkn	2817
shale	2838
shale & lime	2950
lime brkn	3010
shale & lime	3177
lime	3600
shale & lime	3626
Total Depth	

Tops: DF	
Hoebner Shale	3267
Lime wh	3290
Lansing	3311
Conglomerate Cherty	3560
Simpson material	3582
Simpson Dolomite	3602
Simpson Sand	3616
Arbuckle Dolomite	3618

Cable Tool Work:  
Moved in cable tools, bailed,  
drilled cement, cleaned out to  
original rotary depth.