


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

Company - G. W. KEYES DRIG. CO., ET L
Farm - Marshall No. 7

SEC. 25 T. 11 R. 18W
NW SW NT

Total Depth. 3504' DFM
Comm. 6-1-48 Comp. 6-24-48
Shot or Treated.
Contractor.
Issued. 10-30-48

County. Ellis
KANSAS



Elevation. 1952 Ind.

Production. Pot. 1657 Bbls.

CASING:

8 5/8" 1226' RBM
5 1/2" 3306' RBM

Figures Indicate Bottom of Formations.

shale and shells	485
sand	590
pyrite and sand	600 ✓
pyrite	615 ✓
pyrite and sand	623 ✓
pyrite	630 ✓
sand and pyrite	645 ✓
shale and shells	880
red bed	1008
sand and pyrite	1025 ✓
redbed	1100
shale	1150
shale, shells and	
red bed	1208
gypsum	1216
anhydrite	1245
shale and shells	1640
shale and lime	1900
lime	2050
shale and shells	2635
shale sdy	2675
lime and shale	2810
lime	3425
shale	3445
lime	3453
conglomerate	3480
shale	3495
Simpson shale	3504
Arbuckle lime RTD	3506 RBM

CABLE TOOL WORK

Moved in cable tools,
drilled cement, cleaned out
hole to RTD, drilled deeper.

lime 3504
total depth D.F.M.

Tops: Corr. 3' to DF.

Hebner shale	3154
White lime	3173
Lansing	3195
Simpson shale	3479
Arbuckle	3501