

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg. Wichita, Kansas

Company - PHILLIPS PETROLEUM COMPANY  
Farm - Ancobs No. 2

SEC. 26 T. 11 R. 18W  
SW NE NE

Total Depth. 3660' PB 3622'  
Comm. 8-26-47 Comp. 10-22-47  
Shot or Treated. Acidized  
Contractor.  
Issued. 5-1-48

County. Ellis  
KANSAS



Elevation. 1993 feet

Production. Echo. Pot. 2490 BOPD,  
no water

Figures Indicate Bottom of Formations.

clay shale & shells	0-70
shale & shells	540
sand	633
pyrite & rock	664 ✓
pyrite & sand	695 ✓
shale	710
shale & shells	1140
red bed	1210
shale	1217
red bed sdy	1240
gyp	1255
anhydrite	1290
red bed & shale	1305
shale & shells	2020
lime brkn	2170
lime	2360
lime & shale	2425
lime brkn	2585
lime	2730
shale & shells	3035
lime & shale	3100
lime brkn	3140
lime & shale	3501
conglomerate	3519
shale	3555
lime	3660
Total Depth	
Plugged back to 3622'	

Tops:	
Anhydrite	1255
Heebner	3205
Lansing K.C.	3224
Conglomerate	3501
Simpson Shale	3525
Simpson Dolomite	3536
Simpson Sand	3553
Arbuckle	3555

DST 3553½-3558, in Arb., open 45 min.,  
Good blow/9 min., no blow/4 min., slight  
blow/4 min., rec. 34' OCM, no wtr. Drill  
deeper 3563, DST 3556½-63, open 30 min.,  
Rec. 580' oil & 20' mud. BHP 1145#/10  
min., Drill deeper 3660 TD., 5" 3657. PB  
3622, 16 § 3556-60. Acid. w/300 gals.  
Grav. 27.7. 15 § 3560-63, 4 § 3556-60.