

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Hummon Oil, Inc.

SEC. 28 T. 11S R. 18W
LOC. C. NE SW SW

FARM Fisher

NO. 2

TOTAL DEPTH 3616'
COMM. 11/25/66

COMP. 12/11/66


COUNTY Ellis

SHOT OR TREATED

CONTRACTOR H-30, Inc.

ISSUED 3-4-67

KANSAS



CASING

20 10 -3/4" @ 195' w/150 sx. cement

15 8

12 6

13 5

ELEVATION 2076 K.B.

7" @ 3613' w/100 sx. cement; D.V. Tool @ 1397' Arb 3613-16
w/400 sx. cement

PRODUCTION 77 BOPD/ NW

FIGURES INDICATE BOTTOM OF FORMATIONS

Post Rock 50
Post Rock & Shale 195
Shale 710
Sand 760
Shale & Shells 860
Sand 1040
Shale 1371
Anhydrite 1414
Shale 1820
Lime & Shale 2076
Lime & Shale Streaks 2415
Shale & Lime 2625
Lime & Shale 3055
Lime 3575
Lime & Shale 3610
Lime 3616
Rotary T. D. 3616

ELECTRIC LOG TOPS:

Topeka 3061 - 985
Heebner 3286 -1210
Toronto 3309 -1233
Lansing 3331 -1255
Base/K.C. 3565 -1489
Simpson 3587 -1511
Arbuckle 3611 -1535
Log T. D. 3616 -1540
R. T. D. 3616 -1540

SAMPLE TOPS:

Anhydrite 1371
Base Anhydrite 1414

I hereby certify the above and foregoing to be a true and correct log of the above described well, as shown by the drilling reports.

H-30, INC.

By Arlo B. Romer
Arlo B. Romer

STATE OF KANSAS }
SEDGWICK COUNTY } ss.

Subscribed and sworn to before me, a Notary Public in and for said county and state, this 16th day of December, 1966.

Maxine Lampe
Maxine Lampe - Notary Public

My Commission Expires:
December 27, 1967