


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg. Wichita, Kansas

Company - SHELL OIL COMPANY
Farm - F. S. Wasinger No. 1

SEC. 28 T. 11 R. 18W.
NE NE NE

Total Depth. 3613' P.B. 3572'
Comm. 4-27-48 Comp. 5-29-48
Shot or Treated.
Contractor.
Issued. 7-10-48

County. Ellis
KANSAS



CASING:
8-5/8" 1273' Cem. W/600 Sx.
4-1/2" 3610' Cemented

Elevation. 1994' Ind.

Production. 3000 BO

Figures Indicate Bottom of Formations.

surface rocks & shale	150
shale	225
shale & shells	775
shale & sand	1000
shale & red bed	1025
sand & red bed	1081
red bed & shale	1155
red bed	1200
red bed & shells	1265
anhydrite	1305
lime & shale	1320
red bed & sand	1400
shale & sand	1525
shale & shells	2025
shale, shells & salt strk	2115
shale & lime	2720
shale & shells	2745
lime & shale	2770
shale & shells	2800
shale & lime	2835
shale & shells	2946
lime & shale	3110
lime	3180
lime cherty	3215
lime	3430
lime & shale	3455
conglomerate	3508
lime	3514
dolomite 3535 =	3539 SLC
dolomite	3600
dolomite cherty 3615 =	3613
dolomite	3613
Total Depth	

P. B. to 3572'

Tops:
Anhydrite 1262
Topeka 2944
Lansing K. C. 3207
Sooy Conglomerate 3466
Simpson Dolomite 3495
Simpson Shale 3502
Arbuckle Dolomite 3513