


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - SHELL OIL & LARIO OIL & GAS
Farm - F. S. Wasinger No. 2

SEC. 28 T. 11 R. 18W
NE SE NE

Total Depth. 3630' P.B. 3615'
Comm. 7-4-48 Comp. 7-25-48
Shot or Treated.
Contractor.
Issued. 10-9-48

County. Ellis
KANSAS



CASING:
6-5/8" 1345' 4-1/2" 3624'

Elevation. 2059' Ind.

Production. Draw Down Pot. 3000

Figures Indicate Bottom of Formations.

shale	452
shale & lime	512
shale	661
sand	770
lime & shale	840
sand	995
shale & lime	1005
shale & red rock	1162
red bed	1330
redbed & pyrite	1336
shale & red bed	1343
anhydrite	1383
red rock	1546
red rock, sand & shale	1800
shale & lime strks	1938
shale & lime	2035
salt, sand & shale	2187
shale & lime	2233
lime & shale strks	2302
shale	2369
shale & lime	2468
lime strks & shale	2574
lime & shale	2890
shale	2990
lime & shale	3034
shale & lime	3123
lime	3157
lime & shale	3237
lime	3489
lime & shale	3531
shale & chert	3556
conglomerate	3560
dolomite	3564
shale	3574
dolomite	3630
Total Depth	

Plugged Back to 3615'

Tops:	
Topeka	3001
Lime Kansas City	3265
Sooy	3523
Simpson Dolomite	3559
Simpson Shale	3563
Arbuckle	3573