

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas


Company - SHELL & LARIO
Farm - T. S. Wasinger No. 8

SEC. 28 T. 11 R. 18W
NW SW NE
893' fr SL & 330' fr WL NE $\frac{1}{2}$

Total Depth. 3643' PB 3610'
Comm. 12-21-48 Comp. 1-11-49
Shot or Treated. Acidized
Contractor. Marris (cable)
Issued. 4-9-49

County. Ellis

KANSAS



Elevation. 2068 Ind.

Production. State: 2645, no wtr BHP

Figures Indicate Bottom of Formations.

lime	31
lime & shale	331
lime, sand & shale	514
shale, sand & redbed	1025
shale	1090
redbed, pyrite & shale	1353
anhydrite	1388
shale & redbed	1415
redbed, shale & lime	1590
shale	1820
shale, redbed, lime streaks	1887
lime & shale	2093
shale	2186
lime & shale	2486
shale	2528
shale & lime	2689
shale	2694
shale & lime	2794
shale	2886
shale & lime	3051
lime	3073
lime & shale	3239
lime	3300
SIC 3300 = 3301	
lime & shale	3337
lime	3524
shale, conglo. lime	3560
shale & lime	3576
dolomite & shale	3592
dolomite	3609
dolomite & chert	3643
dolomite	3643
Total depth	

Plugged back to 3601'

Tops, Schlumberger:

Topeka	3028
Lansing K. C.	3276
Sooy	3542
Simpson Dolomite	3574
Simpson Shale	3578
Arbuckle	3589

Acid. 3588-93 W/500 gals.

Dowell, Max press. 400#.

Az. 3588-93 & 3595-3600'

W/1000 gals. 700# press.

Perf. data, Lane wells.

Perf. 3588-92 W/23 bullets

Perf. 3592-93 W/7; Perf. 3595-99 W/22

No increase in fill up.

Perf. 3595-3600 W/ 8, no inc. in fillup

Perf. 3600-04 W/22