


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SHELL-LARIO
 Farm- F. S. Wasinger No. 9

SEC. 28 T. 11 R. 18W
 SE NW NE

Total Depth. 3608'
 Comm. 3-22-56 Comp. 4-18-56
 Shot or Treated.
 Contractor.
 Issued. 6-9-56

County Ellis KANSAS



CASING:

8 5/8" 1371' cem w/1000 sx
 5 1/2" 3604' cem w/200 sx

Elevation. 2091' DE

Production. I.P. 114 BO & 214
 BW 24 hrs.

Figures indicate Bottom of Formations.

shale & sand	183	lime, some shale	3480
shale	540	lime	3496
shale & red beds	590	shale, some lime	3505
shale	610	lime	3510
sand	650	lime, some shale	3518
shale	685	lime	3524
shale & sand	725	shale	3528
sand	780	lime, some shale	3542
sand & shale	820	shale, some lime	3552
shale & red beds	895	lime & shale	3560
sand	1035	chert, V.C. shale, some	
shale & red beds	1160	lime	3578
shale & lime	1295	shale	3584
shale & red beds	1363	dolomite, some shale	3593
anhydrite	1397	shale	3603
shale & shells	1540	dolomite	3608 (Rotary & Cable)
shale & lime	2105	Total Depth	
lime & shale	2260		
shaly lime	2373	Tops:	
lime & shale	2440	Topeka	3040
shale	2560	Lansing-Kansas City	3290
shale & shells	2705	Sooy Conglomerate	3552
shale & lime	2950	Simpson	3584
shaly lime & shale	2960	Arbuckle	3603
shale	2966		
shaly lime & shaly sand	2978	Acid - 1000 gallons.	
shale	2984		
lime	2988		
shale & shaly sand	3010		
shaly lime & shaly sand	3040		
lime, shaly	3066		
shale	3070		
lime	3088		
shale	3091		
lime, some shale	3140		
shale, some lime	3156		
lime, some shale	3184		
shale	3190		
lime	3197		
shale, sandy, limey	3208		
lime	3228		
shale	3231		
lime	3268		
shale	3272		
lime	3276		
shale, some lime	3290		
lime	3305		
shale	3312		
lime	3334		
shale, some lime	3342		
lime	3360		
shale	3362		
lime, some shale & chert	3376		
shale, some lime	3384		
lime, some chert & shale	3396		
lime	3413		
lime, some shale	3424		
shale, some lime & chert	3443		
lime, some chert & shale	3460		
shale, some lime	3470		