

PI
KANSAS

**WELL COMPLETION REPORT AND
DRILLER'S LOG**

API No. 15 — 051 — 22,120
County Number

S. 29 T. 11S R. 18 ^{XK} W

Loc. NE NW NW

State Geological Survey
County Ellis
WICHITA, 640 X-1224
N

Operator
CHAMPLIN PETROLEUM COMPANY

Address
6441 N.W. Grand Blvd, Suite 300, Okla. City, OK 73116


Well No. 10 Lease Name Johnson "A"

Footage Location
330 feet from (N) ~~TEX~~ line 990 feet from ~~TEX~~ (W) line

Principal Contractor Red Tiger Drilling Geologist

Spud Date 10-28-80 Date Completed 1-9-81 Total Depth 3750 P.B.T.D. 3700 3689

Directional Deviation Oil and/or Gas Purchaser Koch



Elev.: Gr. 2095

DF _____ KB 2100

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24#	279	Quickset	200	2% CaCl
Production	7-7/8"	5-1/2"	14#	3749	50-50 Pozmix	250	18% salt, .75% CFR2
					Litewate	300	5% Gilsonite/sk

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		3660-66'
TUBING RECORD			2	.52"	3649-53'
Size	Setting depth	Packer set at	1	.52"	3610-22'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized/500 gal. 15% NE acid @ 1/2 BPM	3660-66'
Spot 250 gal. 15% NE acid on perms @ 1/2 BPM @ 200%	3649-53'
Squeeze Arb./125 sx. Common to 2000#	3610-22'

INITIAL PRODUCTION

Date of first production 1-9-81 Producing method (flowing, pumping, gas lift, etc.) Pumping

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	<u>42</u> bbls.		<u>663</u> bbls.	

Disposition of gas (vented, used on lease or sold) Vented Producing interval (s) 3660-66', 3649-53'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
 CHAMPLIN PETROLEUM COMPANY

DESIGNATE TYPE OF COMP.: OIL, GAS,
 DRY HOLE, SWDW, ETC.:
 Single Oil

Well No. 10 Lease Name Johnson "A"

S 29 T 11 S R 18 ^{EX} W


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<u>LOGS</u>				
Gamma Guard	0	3673		
Acoustic Velocity	1700	3696		
<u>DRILLERS LOG</u>				
Surface Soil & Rock	0	28		
Rock, Sand & Shale	28	282		
Shale	282	535		
Red Bed	535	750		
Red Bed, Sand & Shale	750	1380		
Shale	1380	1398		
Anhydrite	1398	1433		
Shale	1433	1805		
Shale & Lime	1805	2077		
Lime	2077	2262		
Lime & Shale	2262	2578		
Lime	2578	3612		
Lime & Arbuckle	3612	3671		
Arbuckle	3671	3750		
RTD		3750		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Signature
	Title
	Date

L2L98

PI

State Geol 29-11-18W
WICHITA, BRANCH

DRILLERS LOG

No. 10 Johnson "A"

CASING RECORD:	COMPANY:	Champlin Petroleum Company	DESCRIPTION:
8 5/8" @ 278.78' w/200 sx cement	CONTRACTOR:	Red Tiger Drilling Company	NE/4 NW/4 NW/4 Sec. 29-T11S-R18W Ellis County, Kansas
5 1/2" @ 3,749' w/250 sx cement	COMMENCED:	October 28, 1980	
	COMPLETED:	November 7, 1980	
TOTAL DEPTH: 3,750'			ELEVATION:

<u>F MATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Rock	0	28	
Rock, Sand & Shale	28	282	
Shale	282	535	
P ' Bed	535	750	
Rock Bed, Sand & Shale	750	1380	
Shale	1380	1398	
Anhydrite	1398	1433	
Shale	1433	1805	
Shale & Lime	1805	2077	
Lime	2077	2262	
Lime & Shale	2262	2578	
Lime	2578	3612	
Lime & Arbuckle	3612	3671	
Arbuckle	3671	3750	
RTD		3750	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 12th day of November, 1980.

Joyce A. Baer
Notary Public