

PI
KANSASWELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 051 — 22121
County Number

Operator

CHAMPLIN PETROLEUM COMPANY

Address

6441 N.W. Grand Boulevard, Suite 300, Okla. City, OK 73116

Well No.

4

Lease Name

Johnson "E"

Footage Location

940

feet from (E) (S) line

2310

feet from (E) (W) line

Principal Contractor

Red Tiger Drilling

Geologist

Spud Date

11-7-80

Date Completed

12-17-80

Total Depth

3670'

P.B.T.D.

3615'

Directional Deviation


Oil and/or Gas Purchaser

Koch

County Ellis

640 Acres

N



Locate well correctly

Elev.: Gr. 1973'

DF 1976' KB 1978'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"		275'	Quickset	200	2% CaCl
Production	7-7/8"	5-1/2"	14#	3669'	50-50 Pozmix	200	18% salt, .75% CFR-2
					Litewate	400	5% Gilsonite
						100 down annulus @ 1100#	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1	.52"	3543-52'
TUBING RECORD					
Size	Setting depth	Packer set at			
2-7/8"	3592'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
NONE	

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
12-13-80		Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	84	bbls.	MCF	337	bbls.
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
Vented			3543-52'		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator CHAMPLIN PETROLEUM COMPANY		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Single Oil
Well No. 4	Lease Name Johnson "E"	
S 29 T 11 S R 18 E W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<u>LOGS</u>				
Gamma-Guard	0	3644		
Compensated Acoustic Velocity	1600	3668		
<u>DRILLERS LOG</u>				
Surface Clay & Post Rock	0	85		
Shale & Sand	85	281		
Shale	281	725		
Sand	725	940		
Shale	940	1272		
Anhydrite	1272	1313		
Shale & Red Bed	1313	1866		
Shale	1866	2092		
Shale & Lime Streaks	2092	2663		
Lime	2663	3573		
Lime & Chert	3573	3647		
Chert	3647	3670		
RTD		3670		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Signature REGULATORY ANALYST Title January 6, 1981 Date
---------------	---

76898

29-11-18W

DRILLERS LOGState Geological Survey
WIC 1111

No. 4 Johnson "E"

CASING RECORD:	COMPANY:	Champlin Petroleum Company	DESCRIPTION:
8 5/8" @ 278'	CONTRACTOR:	Red Tiger Drilling Company	NW/4 SW/4 SE/4
w/200 sx cement	COMMENCED:	November 7, 1980	Sec. 29-T11S-R18W
5 1/2" @ 3,669'	COMPLETED:	November 14, 1980	Ellis County, Kansas
w/200 sx cement			
TOTAL DEPTH: 3,670'			ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
S face Clay & Post Rock	0	85	
Shale & Sand	85	281	
Shale	281	725	
Sand	725	940	
Shale	940	1272	
Anhydrite	1272	1313	
Shale & Red Bed	1313	1866	
Shale	1866	2092	
Shale & Lime Streaks	2092	2663	
Lime	2663	3573	
Lime & Chert	3573	3647	
Chert	3647	3670	
RTD		3670	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 19th day of November, 1980.

James A. Bass
Notary Public