


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - SHELL OIL CO., INC.
 Farm - W. Johnson, Jr. No. 1.

SEC. 30 T. 11 R. 18 W
 SE₄ SE
 330'f SL 330'f EL SE₄¹

Total Depth. 3609'
 Comm. 5-8-44 Comp. 6-6-44
 Shot or Treated. 500 Gals. Acid 3603-09
 Contractor.
 Issued. 9-9-44

County. Ellis
 KANSAS



CASING:
 8 5/8" 1229' Cem.
 4 1/2" 3603' Cem.

Elevation. _____

Production. Pot. 3000B. Drawdown

Figures Indicate Bottom of Formations.

surface soil	60
lime	80
shale	360
shale & shells	609
lime & shale	850
sand & pyrite	875 ✓
sand	1083
shale	1125
sand & pyrite	1155 ✓
shale & red bed	1175
pyrite & shale	1229 ✓
red bed	1395
anhydrite	1430
shale & shells	1942
lime, shale & shells	2010
shale & lime strks	2132
shale & lime	2347
lime	2433
lime & shale	2679
lime	2715
lime & shale	2920
(2920-19 SLCorr.)	
lime & shale	3104
lime	3260
lime & shale	3303
lime	3458
lime & chert	3482
(3482-3485 SLCorr.)	
lime	3607
(3607-06 SLCorr.)	
dolomite	3609
Total Depth	

Tops:

Lansing-K.C.	3319
Sooy	3582
Simpson	3594
Arbuckle	3601