

**State Geological Survey**  
WICHITA, BRANCH

**KANSAS DRILLERS LOG**

API No. 15 — 051 — 20,872  
County Number

S. 31 T11s R. 18 ~~XX~~ <sup>W</sup>  
Loc. C-N 1/2 NE - SW

Operator  
**Beacon Resources Corp.**

Address  
**1000 Century Plaza Wichita, Kansas 67202**

Well No. # 1 Lease Name Pfeifer


Footage Location  
feet from (N) ~~XX~~ line 330 feet from (E) (W) line 660'

Principal Contractor **B & B Drilling, Inc.** Geologist **Richard Roby**

Spud Date Dec. 12, 1972 Total Depth 3697' P.B.T.D.

Date Completed Dec. 18, 1972 Oil Purchaser None

County Ellis  
640 Acres  
N



Elev.: Gr. 2019 2099  
DF 2102 KB 2104

**CASING RECORD**

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8"	20 1/4	246	Common	150	3% CC 2% Gel

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

**TUBING RECORD**

Size	Setting depth	Packer set at

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated

**RECEIVED**  
STATE CORPORATION COMMISSION  
**FEB 25 1974**  
CONSERVATION DIVISION  
Wichita, Kansas

**INITIAL PRODUCTION**

Date of first production \_\_\_\_\_ Producing method (flowing, pumping, gas lift, etc.) \_\_\_\_\_

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio

Disposition of gas (vented, used on lease or sold) \_\_\_\_\_ Producing interval (s) \_\_\_\_\_

**INSTRUCTIONS:** As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas

erator

Beacon Resources Corp.

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. # 1	Lease Name Pfeifer	Dry Hole
--------------	--------------------	----------

S 31 T 11 S R 18 W C - N 1/2 NE - SE SW


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Hole	0	246		
Shale	246	1439		
Anhy.	1439	1472	Anhy	
Shale & Shells	1472	2328		
Shale & Lime	2328	2870		
Shale & Lime	2870	3316		
Lime & Shale	3316	3345		
Lime	3345	3594		
Lime	3594	3697		
Total Depth	3697			
DST #1 3390' - 3445'	480' Salt Water recovery			
DST #2 3530' - 3571'	Recovered 20' Mud			
DST #3 3688' - 3697'	Recovered 5' mud			
No log ran				
<p>We certify the above and foregoing to be true and correct copy of the log on the #1 Pfeifer, located in Ellis County, Kansas</p> <p><i>Bill Pekar</i> President</p> <p><i>Patricia A. Fair</i> Notary Public</p> <p>Subscribed and sworn to before me this 21st. day of December, 1972</p> <p>My commission expires November 22, 1976</p>				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



Signature \_\_\_\_\_

Title \_\_\_\_\_

Date \_\_\_\_\_