

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company - MAZDA OIL CO.
Farm - Henderson "F" No. 3

SEC. 22 T. 11 R. 18W
SE SW SW SW
230' f SL & 410 F WL SW

Total Depth. 3672
Comm. 10-18-50 Comp. 11-13-50
Shot or Treated.
Contractor.
Issued. 8-25-51

County. Ellis

KANSAS



Elevation. 1968

Production. salt Water Disposal

CASING:

8 5/8" 1246' cem w/650 sxs.
5 1/2" 3580' cem w/200 sxs.

Figures Indicate Bottom of Formations.

clay, sand	100
shale, shell	330
shale	550
sand, shale	720
sand	930
shale, sand	1010
shale, shells, red- bed	1228
anhydrite	1275
redbed, shale, shells	1310
redbed, shale	1400
shale, shells	1625
salt, redbed	1800
shale, shells, salt	1840
salt	1860
shale, shells, streaks of salt	2000
redbed, shale, shells, lime	2133
lime, shale	3217
lime	3439
conglomerate	3454
shale, simpson	3481
shale	3493
lime, arbuckle	3520
lime, dolomite, some chert	3555
lime	3672
Total depth	

Scout tops:	
Kansas City	3185
Conglomerate	3439
Simpson	3454
Arbuckle	3493