

WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - LARIO OIL & GAS COMPANY
Farm - Henderson "E" No. 1

SEC. 22 T. 11 R. 18W
CE/2 NE NE

Total Depth. 3575'

Comm. 10-15-46

Comp. 11-6-46


Shot or Treated.

Contractor.

Issued. 1-25-47

County. Ellis

KANSAS



Elevation. 1971' act & rh

CASING:

8-5/8" 1256' Cem w/400 sx
5-1/2" 3575'

Production. Deptho. Pot. 2911
plus 2% wtr.

Figures Indicate Bottom of Formations.

clay & post rock 0-40
shale & shells & sand 316
shale & shells 375
sand & shells 405
shale & shells 500
shale & strks sand 635
shale & pyrite 659
shale 690
sand & shale 740
shale & sand 891
red bed & shale 923
shale & lime shells 1025
shale & lime strips 1110
lime & shale, red bed 1222
red bed & shells 1251
anhydrite 1280
red bed, shale & lime 1466
shale, shells & salt
strks 1670
shale & shells 1795
shale & lime 1918
shale & lime strks 1990
shale & lime 2055
lime & shale 2160
shale 2226
lime 2230
lime & shale 2341
sand 2356
lime & shale 2400
sand & shale & lime 2430
shale 2445
lime 2540
lime & shale strks 2625
shale & strks lime 2675
shale & lime 2740
lime & shale strks 2815
shale & lime 2880
lime & shale 2985
cherty lime & shale 3045
lime & shale 3076
shale 3087
lime & shale 3245
lime 3462
lime & shale 3500
shale 3515
lime 3535
lime & cherty shale 3561
lime 3575
Total Depth

Tops:
Topeka 2948
Heebner 3162
Lansing 3196
Base K. C. 3439
Conglomerate 3458
Simpson sh. 3496
Arbuckle 3516