

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company- OKMAR OIL COMPANY
 Farm- Falconberry "A" No. 4

SEC. 10 T. 11 R. 19W
 W/2 W/2 NW

Total Depth. 3627'
 Comm. 9-8-62 Comp. 9-17-62
 Shot or Treated.
 Contractor. Raymond Drilling Co.
 Issued. 1-5-63

County Ellis
 KANSAS



Elevation. 2072' DF

Production. DRY

CASING:

8 5/8" 157' cem w/125 sx.
 5 1/2" 3627' cem w/200 sx.

Figures Indicate Bottom of Formations.

shale, sand & lime	157
shale & shells	865
sand	1085
shale & shells	1140
shale	1177
red bed	1400
lime	1410
anhydrite	1445
shale & shells	1993
lime & shale	2399
shale & shells	2650
lime & shale	2955
shale & shells	3012
lime & shale	3259
Heebner	3263
lime & shale	3295
lime	3345
lime & shale	3541
Conglomerate-chert	3573
Conglomerate	3591
shale	3615
lime & shale	3619
Arbuckle	3627 RTD
Total Depth	

TOPS:

Sand	865
Anhydrite	1410
Topeka	3012
Heebner	3259
Toronto	3278
Lansing-Kansas City	3299
Conglomerate	3541
Arbuckle	3619