

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- H.V. ELWELL, ET AL
Farm- Louise Sessin No. 1


SEC. 15 T. 11 R. 19W
NE NW SE

Total Depth. 4044'
Comm. 7-8-47
Shot or Treated.
Contractor.
Issued. 5-24-58

DEEPENING RECORD

Comp. 8-8-47

County Ellis
KANSAS



Elevation. 1981

Production. Dry

CASING:

10 3/4" 1287' cem w/500 sxc
7" 3526' cem w/175 sxc

Figures indicate Bottom of Formations.

shale, shells	620	Perforated 60 holes as follows;
sand	675	12 holes - 3455-3459 1/2
shale	720	12 " - 3381 1/2-3386
sand	745	12 " - 3375 1/2-3380
sdv shale	1000	12 " - 3368-3372 1/2
slate, sand	1055	12 " - 3360-3364 1/2
shale, pyrites of iron	1090	
shale, shells	1100	No showings of fluid after shots.
red bed	1265	Acid. w/4500 gals. acid.
gypsum brkn	1278	Perf. 3114-18-12 shots
anhydrite	1315	" 2975-2979 1/2-12 shots.
clay, shale	1590	Testing: Well made 8 1/2 BW 12 hrs.
shale, shells	1900	and scum of oil. Shut down.
lime	2030	
brkn lime	2140	<u>DEEPENING RECORD:</u>
lime, shale	2170	<u>IMPERIAL * OKMAR</u>
lime	2360	Prod-SWDW
lime, shale	2471	T.D. -4044'
shale	2500	Comm-8-19-53
lime, shale	2550	Comp-9-23-53
lime SIM 2600 OK	2665	5 1/2" csg 3529'
lime, shale	2716	Granite Wash 4036
shale	2800	Granite 4043
lime	2832	
shale, lime-lost cir.	2843	
	2870	
shale	2919	
lime	2931	
shale SLM 3201-3195	2945	
lime	3455	
shale, chert	3465	
conglomerate	3469	
cherty conglomerate	3527	
lime	3530	RTD
lime	3532 1/2	
Total Depth		

TOPS:

Topeka	2943	DFM
Heebner	3160	"
Dodge	3183	"
Lansing	3212	"
B/Kansas City	3433	"
Conglomerate	3472	"
Arbuckle	3525	"

SHOWS - RTM

Oil & gas	3174-78
" " "	3128-32
Oil	3368-82
"	3460-63
"	3528-30

Ran Gamma Ray Test. Set Lane
Wells plug 3610.