

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- Okmar Oil Co.

Farm- Gustus

No. 6

SEC. 16

T. 11

R. 19W

C N/2 N/2 NE

Total Depth. 3543'

Comm. 4-6-62

Comp. 4-14-62


Shot or Treated.

Contractor. Leben Drlg.

Issued. 4-6-63

County Ellis

KANSAS



Elevation. 2001 RB

Production. 50 BOPD, 8% W

CASING:

8 5/8" surface casing 169' cem w/125 sx.

5 1/2" casing 3542'

Figures Indicate Bottom of Formations.

post rock & shale	140
shale & shells	770
Dakota sand	890
red bed & shale	1300
Anhydrite	1345
shale & shell	1660
shale & lime	1990
lime & shale	2250
lime	2378
shale & lime streaks	2595
shale & lime	2785
lime	3465
lime & shale (Conglomerate)	3533
lime & shale	3543 RTD
Total Depth	

TOPS:

Heebner	3185
Toronto	3205
Lansing	3224
Sooy Conglomerate	3463
Simpson	3517
Arbuckle	3541