


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
500 East Myrdock, Wichita, Kansas

Company- SKELLY OIL CO.
Farm- Solomon No. 1

SEC. 21 T. 11 R. 19W
SE SE NE

330' f SL 330 f EL NE/4
County Ellis KANSAS

Total Depth. 3507
Comm. 8-14-52 Comp. 4-9-52
Shot or Treated.
Contractor. C. Wentworth Drlg.
Issued. 5-17-52



Elevation. 1974 D.F.

Production. pot. 195 bbls.

Figures Indicate Bottom of Formations.

surface sil, shale & sand	145
shale & sand	296
shale & shells	400
shale & red bed	530
sand	590
shale & shells	1030
shale & red bed	1245
anhyd.	1275
shale & shells	2200
shale & lime	2964
soft oolitic finely xlyn	
lime	2974
lime & shale	3005
lime	3070
shale & lime	3140
lime	3235
lgt fine med. xlyn	
oolitic lime	3239
lime	3321
lgt sucrose oolitic lime	
	3326
lime	3367
gry. finely xlyn soft	
oolitic lime	3370
lime & shale	3500
buff med. to coarse xlyn	
dolo.	3504 RTD
buff med. to coarsely	
xlyn dolo.	3507
Total Depth	

Tops:

Topeka	2964
Heebner shale	3158
Lansing lime	3197
Conglomerate	3447
Simpson shale	3470
Arbuckle lime	3500

Producing form. Arb. 3501-3507

Acid: 4-10-52 200 gals.

3501-3507

4-12-52 500 gals.

3501-3507

By Dowell

3500-3504 good por. & stain

3504-3505 fair por. & stain

3505-3507 fair por. & sat.