


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- SKELLY OIL COMPANY  
Farm- Vine "D" No. 3

SEC. 22 T. 11 R. 19W  
NE NW SE  
330' frm NL, 990' frm WL, SE

County Ellis  
KANSAS



Elevation. 1971 ~~DF~~

Production. pot. 164 bbls

Total Depth. 3503  
Comm. 7-27-51 Comp. 8-19-51  
Shot or Treated.  
Contractor. Claude Wentworth Drlg Co., Inc.  
Issued. 11-10-51

CASING:

8 5/8" 1252' cemw/ 500 sx.  
5 1/2" 3489' cem w/500 sx.

Figures Indicate Bottom of Formations.

surface soil, shale,  
shells 50  
shale, shells 379  
shale, sand 440  
shale, shells 1000  
shale, shells, redbed 1211  
lime, shale 1242  
anhydrite 1285  
shale, shells 1965  
lime, shale 2900  
lime 3060  
lime, shale 3105  
lime 3437  
conglomerate 3466  
shale 3488  
dolomite, light grey  
fine to med. xlyn 3490 RTD  
fine grey xlyn &  
cherty dolomite w/  
little green shale 3503  
Total Depth

Tops:  
Anhydrite 1242  
Topeka Lime 2959  
Toronto 3170  
Heebner shale 3152  
Lansing Lime 3194  
Conglomerate 3437  
Simpson 3466  
Arbuckle Lime 3488

Poor to fair porosity  
& sat. 3488-90  
Rainbow show oil, 10'  
OIH/2 hr 3496-97

Acid Record: 8-19-51  
1000 gals. 3489-3503

Producing Formation:  
Arbuckle Lime 3489-3503