

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


Company- CONTINENTAL OIL CO.  
Farm-R. P. DeVine No. 8

SEC. 23 T. 11 R. 19 W  
SW SW SE  
330' fr SL 2310' fr EL

Total Depth. 3511  
Comm. 1-3-53 Comp. 1-14-53  
Shot or Treated.  
Contractor. Lohmann-Johnson Drilling Co.  
Issued. 2-28-53

County Ellis

KANSAS



Elevation. 1993 RB

CASING:  
10 3/4 208' w/ 175 sx cement  
7 in. 3507' w/ 125 sx cement

Production. Phys. Pump Pot.:  
136 bo., & 34 BW

Figures indicate Bottom of Formations.

surface clay & shale	100
shale & shells	215
shale & sand	550
shale, sand & shells	1125
shale & red bed	1309
anhydrite	1348
shale	1380
shale & shells	1665
shale, pyrite & shells	1917
lime & shale	2065
lime	2196
lime & shale	2465
shale	2516
lime & shale	2680
shale	2776
shale & shells	2852
lime & shale	3302
lime	3460
lime & chat	3505
lime	3511
Total Depth	

SJ TOPS:	
Topeka	2954
Heebner	3184
Lansing	3224
Conglomerate	3466
Arbuckle	3506

DST #1: (Topeka) 2970-89 open 1 hr.  
rec. 50' salt water BHP 960# FFP 0#

Prod. from Arb. open hole 3506-11. Est.  
Phys. Pmp. pot of 136 BO / 34 BW in 24  
hrs. on 2-5-53. Gravity 22°.