

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

500 East Murdock,

Wichita, Kansas

Company- GULF OIL CORPORATION

Farm- Vine

No. 1

C.E. Vine (DLR 10-10-00)

SEC. 23 T. 11 R. 19W

NE NE SW

330' SNL. 310' WEL, SW $\frac{1}{4}$

County Ellis

KANSAS

Total Depth. 3526


Comm. 11-28-51

Comp. 12-22-51

Shot or Treated.

Contractor.

Issued. 5-3-52



CASING:

8 5/8" 1336 cem. w/560 sx. LI

5 1/2" 3521 cem. w/100 sx. LI

Elevation. 2018 K.B.

Production. 2015 (oil) Pot. 6615 bbls.

Figures Indicate Bottom of Formations.

shale	280
shale & gyp	630
shale, gyp & sand	740
shale & gyp	795
shale sdy	1075
red bed & sdy shale	1100
red bed	1314
shale wh	1323
anhyd.	1360
shale	1500
shale & shells	2140
lime & shale	2290
lime & shells	2325
lime	2585
lime & shale	2610
lime	2737
shale & lime	2890
lime	2960
shale & lime	3324
dolo. & lime	3345
lime	3380
lime & shale	3475
lime, shale & chert	3496
lime & shale	3526
Total Depth	

Tops:

Heebner	3190
Toronto	3206
Lansing	3228
Viola	3470
Simpson	3497
Arb.	3519

Az. 500 gals.