

Plotted
K.C.

Plotted Texas CO. Plotted

Location SW c SE
330' E & 330' N of SW c SE.

Sec. 27 T. 11 R. 19W.

Casing Record

20" 10" Farm- Vino No. 1
15 1/2" 8 1/4" Company- Marland Production Co.
12 1/2" 65/8" Contr.-
8/15/28. Comp.- 1/24/29.
Total Depth 3840'. Shot Quarts Between
Correspondence Regarding This Well Should Be Referred to

County- Ellis. FEB 4 1929



Elevation 2132

Initial Production Dry. 77

Figures Indicate Bottom of Formations.

Date Issued. 2/2/1929.

Formation	Depth	Formation	Depth	Formation	Depth
white lime	65	red rock	2415	brown shale	3458
blue slate	180	brkn lime	2442	lime	3530
light slate	225	hrd lime	2448	shale brown &	
blue slate	330	red rock	2460	green	3545
light slate	390	hrd lime	2480	white lime	3650
blue slate	410	brown shale	2490	red rock	3675
light slate	455	hrd lime	2520	hrd lime	3685
lime	465	2 BW PH at 2560'		brkn lime	3710
light slate	520	red rock	2535	Caving badly.	
Hole caving		brkn lime	2575	red rock	3715
red rock	530	red rock	2600	brkn lime	3825
sandy shale	560	HFW at 2600'		Run 3765' 5" csg.	
5 BW PH 545-50'		brkn lime	2610	sand	3835
red rock	580	Run 2610' 8" csg.			
Run 580' of 15 1/2" csg.		hrd lime	2616	sand	3840
white slate	590	blue slate	2621		
red rock	595	hrd lime	2655	Total Depth	3840'
gray slate	620	brown shale	2665		
HFW at 660-70'		hrd lime	2675		
light slate	660	HFW at 2730'			
HFW & caving		blue slate	2730		
brown sand	745	white sft lime	2765		
blue slate	815	hrd lime	2773		
iron	817	Hole caving			
blue slate	850	blue slate	2812		
UR 15 1/2" csg. 830'		UR 8" csg. 2812'			
light sand HFW 880'	1043	lime	2815		
red sand	1128	blue slate	2830		
red rock	1160	Hole caving 15' below			
sft red rock	1170	pipe. 1 1/2" BWPH 2885'			
1200' W.I.H. at 1235'		light slate	2885		
Set 1340' 12 1/2" csg.		brkn lime	2895		
red rock	1340	lgt slate	2930		
lime & iron	1345	drk slate	2955		
red rock	1435	Set 8" csg. 2955'			
7 BW PH at 1375'		sft lime	2965		
Run 1450' 10" csg.		lgt slate	2980		
lime	1485	lime	3000		
red rock	1725	slate & shells	3035		
blue slate	1825/	1 BW PH at 3100'			
salt	2016	slate	3045		
salt & lime shells	2090	lime	3075		
light shale	2105	slate	3135		
red rock	2145	lime	3260		
white lime	2155	1 BW PH at 3100'			
red rock	2214	slate	3270		
blue lime	2224	lime	3380		
red rock	2242	shale	3385		
1 BW PH at 2310'		lime	3400		
white lime	2248	brown shale	3410		
blue shale	2258	Set 3410' 6" csg.			
brkn lime	2330	lime	3420		
blue shale	2337	green shale	3422		
brkn lime	2347	lime	3432		
red rock	2380	shale brown & green	3448		
brkn lime	2400	lime	3453		
		brown			