

27-11-19W

CONTRACTOR'S WELL LOG

OPERATOR: Green & Green  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: VINE "A" #1  
 LOCATION: SW NW SW, Section 27-11S-19W  
 Ellis County, Kansas  
 SPUD DATE: 4/02/81  
 COMPLETION DATE: 4/11/81

0	1319	Sand & Shale
1319	1362	Anhydrite
1362	1421	Sand & Shale
1421	3628	Shale & Lime
	3628	Rotary Total Depth

Spud @ 2:45 p.m., 4/02/81. Drilled 260' of a 12 1/2" hole. Ran 6 jts. of 8 5/8" - 24# casing (tally 248.61) Set @ 255.11. Cemented with 160 sx. of 60-40 posmix, 2% gel, 3% c.c. Plug was down @ 9:30 p.m. Cement did circulate.

T.D. @ 3628'. 15 3/4 hrs. daywork, 1/4 hr. repairs, 8 hrs. lay down drill pipe & run casing. Mud Wt. 9.9, Visc. 42, WL 14.8, pH 6.4, Chl. 54,000, LCM 1 1/2#. Ran 87 jts. of 5 1/2" - 14# casing (tally 3647.84) Set @ 3627'. Ran 10 bbls. salt flush, 200 sacks of common 10% salt. Plug was down @ 7:15 a.m., 4/11/81.

SAMPLE TOPS:

Anhydrite 1319'  
 B/Anhydrite 1362'

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the VINE "A" #1, SW NW SW, Section 27-11S-19W, Ellis County, Kansas.

ABERCROMBIE DRILLING, INC.

BY:   
 Jack L. Partridge, Vice President