


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
508 E. Murdock Wichita, Kansas

Company - SKELLY OIL COMPANY
Farm - T. VINE "A" No. 4

SEC. 27 T. 11 R. 19W
NE NW NW
330' fr NL & 990' fr WL of
NW/4
County. Ellis

Total Depth. 3627 SIM
Comm. 4-2-51 Comp. 4-20-51
Shot or Treated.
Contractor. Claude Wentworth Dlg. Co.
Issued. 8-18-51

KANSAS



CASING:

10 3/4" 1408' cem w/825 ssxs.
7" 3622 1/2 SIM cem w/800 ssxs.

Figures indicate Bottom of Formations.

Elevation. 2114 DF
2116 AB onl.
Production. Pot. 216 bbls. oil

surface soil, shale &
shells 315
shale & shells 680
sand & shale 940
shale & shells 1250
redbed & shells 1315
redbed w/ strks of
sand 1399
Anhy. 1445
shale & shells 1850
shale & lime 2020
shale & shells 2165
shale & lime 2410
sdy lime 2460
lime 2600
lime & shale 3085
lime 3375
lime & shale 3400
lime 3551
lime & shale 3581
lime 3620
simpson shale 3025
grey & brown, medium
coarsely crystalline
dolomite 3630
SIM Correction 3630- 3627
Total depth

Tops:
Anhy. 1399
Topeka 3093
Heebner 3304
Lansing 3343
Conglomerate 3588 SIM
Simpson Series 3597 SIM
Arbuckle 3622 SIM

3622-3627, fair por. & saturation
Rotary Total Depth 3627 SIM

Reamed 9" hole to 13 3/4"