


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- SKELLY OIL COMPANY
Farm- Jensen "B" No. 1

SEC. 34 T. 11 R. 19W
SW SE NE

Total Depth. 3713
Comm. 9-1-53 Comp. 9-14-53
Shot or Treated.
Contractor. Chas. Hulme Drilling
Issued. 10-10-53

County Ellis
KANSAS



CASING:
8 5/8" 1450' cem. w/600 sx

Elevation. 2135' DE

Production. Dry

Figures indicate Bottom of Formations.

surface soil & sand	40
shale & shells	675
sand	860
shale & shells	1140
anhydrite	1485
clay	1650
red bed & shale	2090
shale & lime	2285
lime	2425
lime & shale	2735
shale	2765
shale & lime	2855
shale	2935
lime & shale	3143
fine crystalline lime	3154
lime	3185
lime & shale	3305
crystalline dense lime	3311
lime	3341
lime & shale	3417
crystalline dense lime	3425
lime	3572
crystalline lime	3583
lime	3592
lime & shale	3673
crystalline dolomite	3681
brown crystalline dolo.	3694
crystalline dolomite	3713
Total Depth	

TOPS:

Topeka Lime	3143
Heebner Shale	3341
Toronto Lime	3361
Lansing Lime	3386
Conglomerate	3657
Simpson	3672
Arbuckle Lime	3673

D.S.T. 3676' open 30 min., weak
blow for 3 min., rec. 5'
rotary mud, no oil, BHP
870#

D.S.T. 3678' open 1 hr., fair
blow thruout, rec. 135'
salt wtr, no oil, BHP
835#

D.S.T. 3555' open 30 min. weak
blow for 6 min., rec.
6' drilling mud, BHP
580#

D.S.T. 3675' open 30 min., weak
blow for 8 min., rec. 5'
rotary mud, BHP 0#