


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- J. F. DARBY OIL, C-G DRLG. & OIL TRADING
Farm- Vine "A" No. 3

SEC. 35 T. 11 R. 19W
SW SE NE

Total Depth. 3655'
Comm. 9-16-57 Comp. 9-25-57
Shot or Treated.
Contractor. C-G Drlg.
Issued. 12-14-57

County Ellis
KANSAS



CASING:
8 5/8" 174.01'
5 1/2" 3649'

Elevation. 2106' RB

Production. 232 BOPD

Figures indicate Bottom of Formations.

All meas. taken from top of rotary bushing.

sand-shale	172
shale-sand	650
sand	860
shale-shell	1110
red shale	1436
Anhydrite	1470
shale-shell	2340
shale-lime	3226
lime	3655 RTD
Total Depth	

TOPS:	
Anhydrite (driller)	1436
Topeka	3102
Heebner Shale	3328
Toronto Lime	3349
Lansing	3368
Base Kansas City	3560
Marmaton	3578
Conglomerate	3610
Simpson	3628
Arbuckle	3646

DRILL STEM TESTS:

#1 3400-3450', open 45 min.; weak blow
6 min.; recovered 22' mud; no shows;
BHP 673#, HH 1825#, IBHP 0 (Tool slid)

#2 3649-3655', open 2 hrs., strong steady
blow; recovered 720' oil, bottom 90'
muddy; IBHP 1000#, FBHP 885#; IFP 150#,
FFP 425#; HH 1975#/ all 20 min. open time.