


BRADLEY OIL CO.
Jensen No. 1

SEC. 36 T. 11 R. 19W.
NWc SE

Total Depth. ~~3710~~ ³⁷⁸⁰
Comm. 11-9-37 Comp. 12-4-37
Shot or Treated.
Contractor. The Triangle Drig. Co.
Issued. 12-11-37

DEC 11 1937

County Ellis.



CASING.

12 1/2" 146'5

Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

sand and clay	30	shale and shells	3395	3383-3386 very soft
shale	230	lime and shale mod	3410	little sat.
shale and shells	495	lime and shale hard	3415	
sand, sand rock pyrite of		shale soft	3425	
iron and shells	610 ✓	lime	3450	
shale	625	lime grey hard	3492	
sand	655	lime grey mod	3506	
sand rock shale break	760	lime grey soft	3514	
shale and sand	806	lime grey hard	3550	
sand	1095	lime grey mod	3580	
shale and lime shells	1160	shale	3595	
red bed shale and shells	1265	lime grey hard	3605	
shale and shells	1375	conglomerate	3672	
anhydrite	1410	chert	3681	
shale	1420	Simpson	3692	
shale red bed lime shells	1465	Siliceous	3695	
shale and shells	1735	Top 3693		
sdv shale red bed	1820	siliceous	3740	80 corod
shale	1895	Total Depth.		no shows very dense.
broken lime and shale	1910			
shale and shells	2035			
broken lime and shale	2055			
lime	2075			
lime broken	2115			
shale	2135			
lime and shale	2155			
broken lime	2160			
lime	2220			
lime sdv	2240			
lime broken	2255			
lime	2290			
sdv lime	2295			
shale	2300			
lime	2470			
sdv lime	2480			
lime	2515			
shale	2535			
lime	2630			
lime broken	2770			
shale	2865			
shale and shells	3010			
shale	3020			
lime broken	3025			
shale	3050			
lime broken	3085			
broken lime soft	3100			
lime grey hard	3115			
lime grey mod	3145			
lime grey hard	3195			
lime grey broken mod	3235			
lime soft	3240			
lime grey hard	3273			
lime grey broken mod	3305			
shale and shells	3320			
lime K.C. lime Top	3320			
lime grey hard	3365			