

Fischer Unit #1-5

Operator: Murfin Drilling Company, Inc.

Contractor: Murfin Drilling Company, Inc.

Rig #8

DST #1 3082-3102; (Topeka) 30-45-60-90; IF: 2" blow increasing; Rec. 40' MW, 184' SW; Rw .08, 70°, (99,000 ppm), BHT: 103°; FP: 20/67, 71/128; SIP: 837-826; HP: 1461-1405.

DST #2 3322-3365 (LKC A) 30-45-60-90; Rec. 1104' GIP, 372' CGO, 310' MCGO; FP: 87/132, 143/245; SIP: 929-910; HP: 1159-1161; GRAV. 32°; BHT 111°.

DST #3 3361-3410' (LKC D,E,F zones) 30-45-30-60; IF: stng bl obb, no blow back; Rec. 62' GIP, 325' MCGO (10% G, 70% O, 20% M), 248' OCWGM (10% G, 20% O, 15% W, 55% M), 124' OCW (20% O, 80% W), 310' SW; (.09 @ 70°, 85,000 ppm cl 112°); FP: 72/308, 316/440; SIP: 678-677; HP: 1639-1579.

DST #4 3422-3514' (LKC H, I, J, K zone) 30-45-60-90; IF: stn bl obb 3 min, sm bl back; Rec. 30' CGO (10% G, 90% O), 30' MCGO, 248' OCM (5% O, 95% M), 124' SOCW (2% O, 85% W, 13% M), 186' SW (.11 @ 70°, 70,000 ppm, 109°); FP: 74/197, 200/306; SIP: 785-791; HP: 1721-1626.

DST #5 3620-3630' (Arb) 30-45-60-90; IF: stng bl, Rec. 90' GIP, 92' CGO, 154' OCW (40% O, 60% W), 216' SW (Rw .25 @ 60°, 32,000 ppm, BHT: 117°); FP: 45/191, 191/241; SIP: 244-245; HP: 1779-1765.

DST #6 3636-3655' (Arb) 30-45-60-90; Rec. 90' GIP; 784' CGO (80% O, 20% G), 92' MCO; GRAV. 38°; FP: 22/168, 170/347; SIP: 1162-1164; HP: 1800-1752.