

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

502 East Murdock,


Wichita, Kansas

Company- MAGNOLIA PETROLEUM CO.
Farm- Genevieve Richards No. 1

SEC. 6 T. 11 R. 20W
C E $\frac{1}{2}$ SE NE

Total Depth. 3691
Comm. 1-16-52 Comp. 1-31-52
Shot or Treated.
Contractor. Barnett Drlg. Co.
Issued. 3-29-52

County Ellis
KANSAS



CASING:

13 3/8" 198' cem.
6 5/8" 3689'

Elevation. 2071' DF

Production. 342 BO/24 hrs.
& no wtr

Figures indicate Bottom of Formations.

surface soil & clay	10
sand	65
clay & sand	100
shale & shells	198
shale	298
shale & shells	660
sand	780
shale & shells	955
sand	1000
sand & shale	1195
shale & shells	1530
anhydrite	1568
shale & shells	1620
shale, shells & lime	2095
shale & lime	2455
lime	3691
Total depth	

Tops:

Lansing	3362
Conglomerate	3622
Simpson	3663
Arbuckle	3677

Cored 3673-77, rec. 3' grn sdy
shale w/some pyrite, 2' sdy dolo.,
last 3" sat. w/oil.
Cored 3677-82 1/2, rec. 4' 2"
dolomite w/spotted saturation,
Cored 3684-90, rec. 3' dolo.
spotted w/oil saturation.
Ran Schlumberger