


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **MAGNOLIA PETROLEUM CO.**
 Farm- **Genevieve Richards** No. **2**

SEC. **6** T. **11** R. **20W**
 CW/2 SE NE
 70' E of CW/4 SE NE

Total Depth. **3684**
 Comm. **9-26-52** Comp. **11-8-52**
 Shot or Treated.
 Contractor. **Barnett Drlg.**
 Issued. **12-27-52**

County **Ellis**
KANSAS



CASING:
 8 5/8" 195' cem. w/150 sx.
 5 1/2" 3673 cem. w/200 sx.

Elevation. 2059 D.F.
2061 (200)
 Production. Pmp. 36 B0 no wtr.

Figures Indicate Bottom of Formations.

sand & clay	160
shale & shells	630
sand & shale	900
shale & shells	1500
red bed	1515
anhyd.	1553
shale	1910
shale & lime	3235
lime	3684
Total Depth	

Tops:
 Heebner 3311
 Lansing-K.C. 3346
 Congl. 3513
 Simpson 3648
 Arbuckle 3672

R.T.D. 3675
 D.D. 3677 & bailed 4 GOPH, 7 hrs, no wtr.
 D.D. 3679, acidized w/3000 gals., tested
 3/4 BOPH, no wtr. 10 hrs.
 D.D. 3684, az. w/3000 gals.