

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

502 East Murdock,


Wichita, Kansas

Company—MAGNOLIA PETROLEUM COMPANY  
Farm—Genevieve Richards<sup>B</sup> No. 1

SEC. 6 T. 11 R. 20W  
NE NW SE

Total Depth. 3784  
Comm. 4-24-52 Comp. 5-13-52  
Shot or Treated. Acidized  
Contractor. Barnett Drilling, Inc.  
Issued. 7-19-52

County Ellis  
KANSAS



Elevation. 2013 D.F.

Production. 10 BOPD, no wtr

Figures Indicate Bottom of Formations.

sand, clay	125
shale	560
sand	730
shale	820
shale, sand	1240
sand, shale	1280
sand, red bed	1490
anhydrite	1545
shale, shells	1665
shale, lime	1990
shale, shells	2125
shale, lime	2345
shale, shells	2435
lime	2645
shale,, shells	2730
lime	2890
shale, shells	2980
shale, lime	3115
shale, shells	3175
lime	3350
lime, chert	3385
lime	3630
shale	3635
red bed	3685
shale	3690
shale, lime	3784
Total Depth	

Tops:  
Heebner 3299  
Lansing 3332  
Penn. Cherty Congl. 3696  
Arbuckle 3722

PB 3592, perf. 3530-40  
w/46 sh., bail 3 BWPH,  
4 hrs, NSO.  
Acidized w/2000 gals., bailed  
1/2 bailer acid water, 1/4 bailer  
oil.  
Acidized w/4000 gals., P 10 BO, NW