

**WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY**  
 508 East Murdock, Wichita, Kansas


Company- IMPERIAL OIL OF KANSAS, INC.  
 Farm- Fischer "A" No. 1

SEC. 9 T. 11 R. 20W  
 NW NW SW

Total Depth. 3670'  
 Comm. 6-6-59 Comp. 6-17-59  
 Shot or Treated.  
 Contractor. Imperial Oil of Kans.  
 Issued. 11-7-59

County Ellis

KANSAS



Elevation. 2034' RB

Production. Dry

**CASING:**

8 5/8" 216' cem w/175 sx.

Figures indicate Bottom of Formations.

surface sand & clay	70
sand & shale	148
shale-shells & sand	890
sand & shale	1000
Dakota sand	1215
shale & shells	1430
Anhydrite	1505
shale & shells	2305
shale & lime	3305
lime	3545
shale & lime	3605
lime & chert	3640
Arbuckle	3670 RTD
Total Depth	

TOPS:	SAMPLE	ELECTRIC
Anhydrite	1469	1467
Topeka	3081	3078
Heebner	3296	3292
Toronto	3320	3316
Lansing	3336	3332
Base Kansas City	3568	3564
Conglomerate	3602	3599
Arbuckle	3642	3640

DST #1 3328-65', op 1 hr., rec. 10' mud,  
 BHP 960#.

DST #2 3360-85', op 1 hr., rec. 5' mud  
 BHP 0#.

DST #3 3382-3400', op 1 hr., rec. 10'  
 mud w/a few specks oil, BHP 780#.

DST #4 3455-3545', op 1 hr., rec. 10'  
 mud, BHP 780#.

DST #5 3597-3610', op 1 hr., rec. 3'  
 mud w/specks oil, BHP 0#.

DST #6 3628-40', op 1 hr., rec. 70' mud,  
 BHP 690#.

DST #7 3643-49', op 2 hrs., rec. 190'  
 slightly oil cut salt water, 5% to 6% oil,  
 BHP 1060#.