


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CARL TODD DRILG. CO.
Farm- Yohe No. 1

SEC. 10 T. 11 R. 20W
SW SW SE

Total Depth. 3710'
Comm. 5-8-56 Comp. 5-17-56
Shot or Treated.
Contractor.
Issued. 6-16-56

County Ellis
KANSAS



CASING:
10 3/4" 252' cem w/185 sx

Elevation. 1999' KB

Production. Dry

Figures indicate Bottom of Formations.

sand and gravel	30
shale and shells	252
shale and shells	475
sand and shale	515
sand	530
shale and sand	775
sand	875
sand and shale	1100
red bed and shale	1235
red bed and shale	1438
anhydrite	1475
shale, shells, salt	1610
shale and lime	1930
lime and shale	2225
sandy lime and shale	2380
shale and lime	2860
lime and shale	3015
shale	3045
lime and shale	3225
shale and lime	3310
lime	3366
lime	3497
lime and shale	3560
lime, shale, chert	3603
Conglomerate	3645
Simpson	3660
lime	3710 RTD
Total Depth	

Tops:	
Topeka	3060
Heebner	3276
Toronto	3300
Lansing	3316
Base Kansas City	3537
Conglomerate	3586
Simpson	3643
Arbuckle	3660

DST #1 3470-97', weak blow 5 min., flushed tool in 20 min., open 1 hr., rec. 15' mud, no shows IF 0, FF 0, BHP 0.