

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- VEEDER SUPPLY COMPANY ET AL
Farm- ~~Irwin~~ No. 2

SEC. 11 T. 11 R. 20W
SE NW NW


Irwin
(DEL 11-08-06)

Total Depth. 3653
Comm. 1-20-55 Ccmp. 2-1-55

Shot or Treated.
Contractor. Veeder Supply & Development
Issued. 3-19-55

County Ellis

KANSAS



Elevation. 2045 R.B.

Production. 1470 bbls.

CASING:

8 5/8" 210 cem. w/135 sx.
5 1/2" 3645 cem. w/150 sx.

Figures indicate Bottom of Formations.

sand, yellow chalk 45
chalk, yellow, blue
shale 125
shale blue 210
shale & shells 900
sand strks 1050
sand 1200
shale, shells, red
bed 1456
Anhyd. 1502
shale & shells 2050
shale & lime strks 2140
shale 2235
lime & shale 3070
lime 3134
lime & shale 3195
lime 3245
cherty lime 3277
lime 3335
lime & pyrite 3370 ✓
lime 3464
cherty lime 3519
lime 3625
cherty lime 3642
lime 3653
Total Depth

Tops:
Topeka 3070
Heebner 3285
Toronto 3318
Lansing 3327
Congl. 3575
Simpson 3625
Arbuckle 3642