

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


Company. IMPERIAL OIL OF KANSAS, INC.
Farm- Fischer "B" No. 1

SEC. 16 T. 11 R. 20W
NE NE NW

Total Depth. 3685'
Comm. 6-18-59 Comp. 6-27-59
Shot or Treated.
Contractor.
Issued. 11-7-59

County Ellis

KANSAS



CASING:

8 5/8" 220' cem w/150 sx.

Elevation. 2032' KB

Production. Dry

Figures Indicate Bottom of Formations.

shale	218
shale & shells	940
Dakota sand	1155
red bed & shale	1458
Anhydrite	1504
shale	1575
shale & shells	2020
shale & lime	3259
lime	3665
lime & Conglomerate	3685 RTD
Total Depth	

TOPS:	SAMPLE	ELECTRIC
Anhydrite	1466	1464
Heebner	3321	3319
Toronto	3345	3344
Lansing	3362	3359
Base Kansas City	3584	3582
Cherty Marmaton	3628	3628
Cherty Conglomerate	3667	3665

DST #1 3508-31', op 1 hr., rec. 10' very
slightly oil cut mud, BHP 380#.