

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- D.R. LAUCK OIL CO. INC.
 Farm- Rand No. 1


SEC. 29 T.11 R. 20W
 SW SW SW

Total Depth. 3879'
 Comm. 3-10-54
 Shot or Treated.
 Contractor.
 Issued. 11-20-54

Comp. 3-25-54

County Ellis

KANSAS



Elevation. 2267 DF

Production. Prop. 50 BO/no wtr.

CASING:

8 5/8" 126' w/125 sx cem.
 5 1/2" 3875' cemented

Figures indicate Bottom of Formations.

surface clay-sand	80
shale	126
shale-s hells-sand	745
sand	975
shale-sand	1350
shale-red bed	1679
anhydrite	1725
s hale-shells	2200
shale-lime	2739
sand	2803
shale-lime	2940
lime	2970
shale-lime	3460
lime	3879
Total Depth	

TOPS:

Topeka	3304
Heebner	3526
Toronto	3549
Lansing	3566
B/Kansas City	3800
Marmaton chert	3851
Arbuckle	3873

DST #1 3592-3624- good blow
 for 1 hr.; rec. 200' slightly
 oil cut wtr.; BHP 1210#. 20
 min.; IFF 35# FFP 110 #.

DST #2 3715-3747 weak blow
 for 3 min. open 30 min. rec.
 10' mud; BHP 800#.