


**WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY**  
 508 East Murdock, Wichita, Kansas

Company- D. R. LAUCK OIL CO., INC.  
 Farm- Rand No. 2

SEC. 29 T. 11 R. 20W  
 NW SW SW

Total Depth. 3925'  
 Comm. 10-16-59 Comp. 10-25-59  
 Shot or Treated.  
 Contractor.  
 Issued. 2-13-60

County Ellis KANSAS



**CASING:**

8 5/8" 200' cem. w/150 sx.  
 5 1/2" 3924' cem. w/600 gal. Latex

Elevation. 2261 DF

Production. 25 BOPD

Figures Indicate Bottom of Formations.

sand clay & shales	70
shale & shells	200
chalk	240
shale	830
sand	915
sandy shale & shells	1400
red bed & shells	1540
shale & shells	2260
shale & broken lime	2935
shale & lime	3355
lime & shale	3440
lime	3840
lime, shale & chert	3880
lime	3925RTD
Total Depth	

TOPS:	SAMPLE	SCHLUMBERGER
Heebner	3518	3517
Toronto	3543	3542
Lansing	3557	3556
Base Kansas		
City	3790	3792
Marmaton Chert	3845	3844
Arbuckle	3872	3874

DST #1 (M-D) 3730-3745 Open 1 hr,  
 good blow 1 hr; recov. 1530' fluid;  
 480' muddy oil; 960' oil, 120'  
 water; IFP 165# FFP 560#; BHP  
 1310# in 20 min.