


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
 508 East Murdock, Wichita, Kansas

Company-D. R. LAUCK OIL CO., INC.  
 Farm- Rand No. 3

SEC. 29 T. 11 R. 20W  
 SE 25 20

Total Depth. 3957'  
 Comm 10-26-59 Comp. 11-7-59  
 Shot or Treated.  
 Contractor.  
 Issued. 2-13-60

County Ellis KANSAS



CASING:  
 10 3/4" 214' cem. w/150 sx.  
 7" 3910' cem. w/400 gals. Latex

Elevation. 2256 DF

Production. 35 BOPD

Figures indicate Bottom of Formations.

sand, clay & shells	70
shale & shells	214
chalk	230
shale	820
sand	900
shale & shells	1200
sand & shale	1350
red bed & shells	1667
anhydrite	1675
lime & shale	1765
shale & shells	2255
shale & lime	2650
lime & shale	3045
shale & shells	3170
shale & lime	3275
lime & shale	3365
lime	3485
lime	3550
lime	3805
conglomerate	3850
lime	3957R1D
Total Depth	

TOPS:	SAMPLE	SCHLUMBERGER
Anhydrite (Drillers)	1667	
Heebner	3511	3510
Toronto	3537	3534
Lansing	3550	3549
Base Kansas		
City	3790	3784
Marmaton		
Chert	3836	3832
Arbuckle	3861	3859

DST #1 (M-D) 3890-3895; open 30 min.  
 weak blow 8 min; recov. 20' mud.  
 IFP 15# FFP 35# BHP 610# in 20 min.

~~DST #2 (M-D) 3895-3905 open 1 hr;  
 strong blow 45 min; and died;  
 recov. 2640' oily water; estimated  
 5% oil; IFP 580# FFP 1140#, BHP  
 1170# in 20 min.~~