


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MALLONEE DRILLING CO.
Farm- Nicholson "A" No. 1

SEC. 30 T. 11 R. 20W
NW NW NE

Total Depth. 3853'
Comm. 10-30-57 Comp. 11-13-57
Shot or Treated. \\
Contractor. Mallonee Drlg. Co.
Issued. 8-1-58

County Ellis
KANSAS



Elevation. 2235' RB

Production. 25 BOPD

CASING:

8 5/8" 213' cem w/125 sx.
1/2" 3852' cem w/100 sx.

Figures indicate Bottom of Formations.

soil & post rock	30
shale & shells	213
shale & sand	990
sand	1340
red bed	1405
red bed & shale	1642
Anhydrite	1695
shale & shells	1985
shale & salt	2100
shale & shells	2200
lime & shale	2620
lime w/shale strks	2685
lime & shale	3155
lime	3245
lime & shale	3350
lime	3563
lime & shale	3585
lime	3745
lime & shale	3785
Conglomerate	3814
lime	3829
lime & shale	3840
Conglomerate	3849
lime	3853 RTD
Total Depth	

TOPS:

Anhydrite	1695
Topeka	3266
Heebner	3482
Toronto	3506
Lansing	3518
Conglomerate	3776
Arbuckle	3849

DRILL STEM TESTS:

#1 3579-3608, op 1 hr, rec. 120' heavy oil cut mud, BHP 895#.

#2 3608-3635, op 1 hr, rec. 38' muddy salt water, BHP 1100#.

#3 3690-3730, op 1 hr, rec. 10' heavy oil cut mud, 160' oil cut mud, BHP 1025#.