


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- D.R. LAUCK OIL CO. INC.
Farm- Wishnuck No. 1

SEC. 30 T. 11 R. 20W
SW SE SE

Total Depth. 3856'
Comm. 5-21-54 Comp. 6-9-54
Shot or Treated.
Contractor.
Issued 8-28-54

County Ellis
KANSAS



Elevation. 2248' D F

Production. Pmp. 50 BO/no wtr

CASING:

8 5/8" 154' w/125 sx cem.
5 1/2" 3850' w/125 sx cem.

Figures indicate Bottom of Formations.

sand	72
shale-shells	580
shale-shells-sand-	
stone	815
sand	900
shale-sandstone	1190
sand-shale stone	1220
sand	1360
shale-shells-red bed	1660
anhydrite	1715
red bed-shalls	1795
shale-shells	2295
lime-shale	2765
lime-shale-sandstones	2865
sand	2798
shale-lime	3130
shale-shells	3405
lime-shale stones	3442
lime	3853
Arbuckle	3856 RTD
Total Depth	

TOPS:

Heebner	3507
Toronto	3527
Lansing-Kansas City	3544
Base Kansas City	3771
Marmaton Chert	3820
Arbuckle	3848

DST- #1- 3849-3853
open 30 min., weak blow for
4 min. Rec. 12' mud with
a few oil specks, no wtr.;
BHP 1000#, 15 min.

DST- #2- 3850-3856 RTD
weak steady blow 1 hr.;
rec. 30' very heavily oil
cut mud & 120' free oil.
No wtr. BHP 740#, 20 min.