

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas


Company-D.R. LAUCK OIL CO., INC.
Farm-Wishnuck No. 4

SEC. 30 T. 11 R. 20W
NW SE SW

Total Depth. 3916'
Comm. 10-5-59 Comp. 10-15-59
Shot or Treated.
Contractor.
Issued. 2-13-60

County Ellis

KANSAS



Elevation. 2270 DF

Production. 33 BOPD

CASING:

8 5/8" 205' cem. w/150 sx.
5 1/2" 3915' cem. w/600 gals. Latex

Figures Indicate Bottom of Formations.

surface clay	20
sand & gravel	60
shale & shells	206
chalk	250
blue shale	695
sand	770
red bed	825
sand	915
shale & shells	1430
red bed & shells	1800
shale & shells	2240
shale & broken lime	2340
shale & lime	2525
shale & shells	2575
lime & shale	2635
shale & shells	3040
shale & broken lime	3215
shale & lime	3345
lime & shale	3446
lime	3790
lime & shale	3845
lime & chert	3870
lime	3916 RTD
Total Depth	

TOPS:	Sample	Schlumberger
Anhydrite	1682	1683
Heebner	3530	3526
Toronto	3551	3554
Lansing	3568	3566
Base Kansas City	3788	3792
Marmaton Chert	3838	3842
Arbuckle	3865	3868

DST #1 (M-D) 3615-3625 Open 1 hr.
Weak blow 1 hr. Rec. 390' mdy. wtr.;
IFP 50#; FFP 190#; BHP 640# in 20 min.

DST #2 3730-3750, Open 1 hr. Weak blow
11 min.; Rec. 12' mud with specks of
oil. FPs 0#; BHP 155# in 20 min.