


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company STANOLIND OIL & GAS CO.
Farm. John Huck "A" No. 2

SEC. 31 T. 11 R. 20W
C W/2 SE NW
660' N of SL, 990' W of EL

County Ellis

KANSAS



Elevation. 2247 RB

Production. 84 BOPD, NW

Total Depth. 3836
Comm. 10-13-55 Comp. 11-5-55
Shot or Treated.
Contractor.
Issued. 1-7-56

CASING:
8 5/8 @ 210' w/ 150 sx cmt.
5 1/2 @ 3829' w/ 750 sx cmt.

Figures indicate Bottom of Formations.

surface clay & sand	130
shale & shells	210
shale	1460
red bed & shale	1663
anhydrite	1705
shale & shells	1843
shale	2220
shale & lime	3550
lime	3665
hard lime	3678
lime	3685
lime & shale streaks	3710
lime	3799
lime & shale	3826
lime	3836
Total Depth	

TOPS:
Heebner 3489
Lansing 3528
Arbuckle 3828

DST #1: 3822-31, open 1 hr. SI 20
min. rec. 5' drlg. mud, no show,
IFP & FFP 0#, BHP 60#.

Core #1; 3828-29; rec. 8"
Core #2; 3831-36, rec. 5'

CO to bottom, testing 10 GOCMPH,
500 gal. XXF32 15% acid/35 min. rec.
load & acid wtr. swbng. & testing
15 hrs. avgd. 1.67 BOPD, no wtr.
Production testing, 45.90 BNO, no
wtr./23 hrs.