

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. D. R. LAUCK OIL CO., INC.
Farm. Keagy 'A' No. 1

SEC. 32 T. 11 R. 20W
NW NW NW

Total Depth. 3994

Comm 8-22-54

Comp. 9-2-54


Shot or Treated.

Contractor.

Issued. 10-16-54

County Ellis

KANSAS



Elevation. 2265 DF

Production. Dry

CASING:

8 5/8 148' w/ 125 sx cmt.

Figures Indicate Bottom of Formations.

sand & shale	148
shale	535
shale & sand	740
sand	965
sand & shale	1165
sand	1410
shale & red bed	1675
anhydrite	1725
shale, shells & red bed	1900
shale & shells	2505
lime & shale	2610
brown lime & shale	2720
lime & shale	2800
sand	2815
lime & shale	2820
lime	2902
lime & shale	3480
lime	3883
conglomerate	3985
Arbuckle	3994
Total Depth	

TOPS:

Anhydrite	1675
Topeka	3308
Heebner	3530
Toronto	3554
Lansing	3572
Base KC	3805
Marmaton chert	3858
Cherty conglomerate	3878
Arbuckle	3985

DST #1: 3620-32, open 30 min. weak
blow 2 min. rec. 5' mudm BHP 1180#