

35-11-20W

CHIEF DRILLING CO., Inc.

Drilling Contractors - Oil Producers

~~XXXXXX CENTURY PLAZA~~
 151 N. Main Suite #700
 WICHITA, KANSAS 67202

V. RICHARD HOOVER
 PRESIDENT

DAILY DRILLING REPORT
 API: 15- 051-24,363
 RIG #1

(316) 262-3791

HALL #1 (#2424)
 SE NE SW 35-11S-20W
 Ellis County, Kansas

CONFIDENTIAL ELEVATION: 2142 GR
 2144 DF
 2147 KB

12-03-85 Moved in on location, spudded in @
 5:00 pm, ran 6 jts. 254' new 20#
 8 5/8" casing set @ 257', cemented
 w/170 sks 60-40 posmix, 2% gel, 3%
 cc., completed @ 11:30 pm.

12-04-85 Drilling out the plug

12-05-85 Drilling @ 1866'

12-06-85 Drilling @ 2762'

12-07-85 DST #1 3226-3268 (Topeka Top) 45-60-
 45-60 (tool slid 4') wk blow Rec. 40'
 MCW; 210' MW, 68,000 ppm IBHP: 1013#
 FBHP: 1002# IFP: 46-69 FFP: 104-104

12-08-85 Drilling @ 3498' TD. 3600' Ran E-log

12-09-85 Plugged w/180 sks 60-40 posmix, 6% gel
 1-sx. flow seal, 1st plug @ 1562' w/20
 sks. 2nd plug @ 850' w/100 sks, 1 sk
 of flowseal, 3rd plug @ 290' w/40 sks
 solid bridge plug @ 40' w/10 sks. 10
 sks in RH Started @ 3:15 am completed
 @ 4:45 Dave Wann District #6 State Plugger

FORMATION TOPS:

Anhydrite	1557 +	590
Base Anhydr.	1598 +	549
Topeka	3204 -	1057
Heebner	3426 -	1279
Toronto	3447 -	1300
Lansing KC	3467 -	1320
RTD	3600 -	1453

E-LOG TOPS:

Anhydrite	1545 +	602
B/Anhydr.	1591 +	556
Topeka	3200 -	1053
Heebner	3422 -	1275
Toronto	3444 -	1297
Lansing KC	3460 -	1313
LTD	3597 -	1450

DEC 20 1985
 State Geological Survey
 WICHITA BRANCH

STATE GEOLOGICAL SURVEY DIVISION

DEC 16 1985

CONSTRUCTION DIVISION
 Wichita, Kansas