

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL OF KANSAS, INC.
 Farm- Spaulding "B" No. 2

SEC. 1 T. 11 R. 21W
 NE NE NE


Total Depth. 3623' RTD 3637' CTTD
 Comm. 11-20-56 Comp. 12-14-56

County Trebo KANSAS

Shot or Treated.

Contractor. Imperial Oil of Kansas

Issued. 2-2-57



CASING:

8 5/8" 187' w/150 sx cem.

Elevation. 2052' RB

Production. 261 BOPD no wtr.

Figures indicate Bottom of Formations.

surface sand	
& clay	187
sand & shale	990
Dakota Sand	1190
shale & shells	1240
shale & red bed	1498
Anhydrite	1541
shale & shells	2040
shale	2160
shale & lime	3030
lime	3623 RTD
Total Depth	
CTTD	3637

TOPS	
Anhydrite	1498
Heebner	3288
Toronto	3310
Lansing	3324
Conglomerate	3584
Simpson	3612
Arbuckle	3621

DRILL STEM TEST

DST #1 3352-78 op. 1 hr.
 Rec. 30' mud. B.H.P. 30#.

DST #2 3394-3420 op. 2 hrs.
 Rec. 180' gas, cut oil, 90'
 wtr. FP 0#-93#. B.H.P. 1175#.

DST #3 3496-3512 op. 1 hr.
 Rec. 20' mud w/tr. oil
 B.H.P. 125#

Dst #4 3511-33 op. 2 hrs.
 Rec. 320' gas, 110' heavy
 oil cut mud B.H.P. 800#.

DST #5 3607-17- op 2 hrs.
 Rec. 540' gas, 360' oil,
 120' heavy oil cut mud.
 B.H.P. 775#.