


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL OF KANSAS, INC.
Farm- Spaulding "C" No. 3

SEC. 1 T. 11 R. 21W
C N/2 N/2 SW

Total Depth. 3659'
Comm. 2-11-58 Comp. 2-17-58
Shot or Treated.
Contractor. K & E Drilling, Inc.
Issued. 6-21-58

County Trego
KANSAS



Elevation. 2073' DF

Production. 161 BOPD, 10% Wtr.

CASING:

8 5/8" 217' cem w/175 sx.
5 1/2" 3648' cem w/100 sx.
(DV @ 1150 w/100 Bbls Kempac)

Figures Indicate Bottom of Formations.

cellar	8
soil & clay	20
sand	35
shale	490
shale & shells	660
sandy shale	985
sand	1260
Anhydrite	1560
shale & shells	2050
shale & lime	2295
lime & shale	2465
shale & lime	2680
lime & shale	2830
shale & lime	3270
lime	3554
lime & shale	3590
lime	3630
lime & shale	3649 RTD
lime	3659
Total Depth	

TOPS: SAMPLE

Anhydrite	1520
Heebner	3308
Toronto	3330
Lansing	3346
Base Kansas City	3570
Cherty Conglomerate	3615
Arbuckle	3645

DST #1 3414-37, open 1 hr, rec. 60' gas,
1080' muddy salt water, BHP 1180#.

DST #2 3528-54, op 1 hr, rec. 10' drilling
mud, BHP 30#.