


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- **IMPERIAL OIL OF KANSAS, INC.**
 Farm- Spaulding "CD" No. 5

SEC. 1 T. 11 R. 21W
 C N/2 SW SW

Total Depth. 3658'
 Comm. 6-10-58 Comp. 6-20-58
 Shot or Treated.
 Contractor. Imperial Oil of Kansas, Inc.
 Issued. 3-28-99

County Trego
 KANSAS



Elevation. 2061' RB

Production. 76 BOPD, NW

CASING:

8 5/8" 226' cem w/150 sx.
 5 1/2" 3650' cem w/100 sx.

Figures indicate Bottom of Formations.

shale	226
shale & sand	1000
Dakota sand	1190
shale & red beds	1420
shale & shells	1504
Anhydrite	1547
shale & shells	2050
shale & lime	3350
lime	3658 RTD
Total Depth	

TOPS: SAMPLE

Anhydrite	1508
Heebner	3309
Toronto	3329
Lansing	3348
Base Kansas City	3578
Conglomerate	3626
Arbuckle	3644

No electric log run.

DST #1 3608-48', op 1 hr., rec. 10' drlg.
 mud, ICIP 20#, BHP 30#.

DST #2 3648-53', op 1 hr., rec. 15'
 slightly oil cut mud, ICIP 1200#, BHP
 1030#.

DST #3 3653-58', op 3 hrs., rec. 85'
 very heavily oil cut mud, ICIP 1150#,
 BHP 940#.